2025 POND MAINTENANCE





CITY PROJECT #WR259001



PLYMOUTH, MINNESOTA

VICINITY MAP





I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

DANIEL T. ELEMES

PROJECT No. 24343

DATE: 10.31.2024 LIC. NO. 55420

SHEET LIST TABLE

SHEET NUMBER SHEET TITLE

G-001 COVER

C-001 LEGEND

C-002 GENERAL NOTES

C-101 SITE ACCESS AND TEMPORARY EROSION CONTROL

C-201 DETAILS

C-601 PLAN AND PROFILE

C-602 TURF RESTORATION PLAN

++++

0

(A)

8

**** # #** \

∘12°

EXISTING PVC/WOOD FENCE

EXISTING TREE/TREE CLUSTER

FXISTING CLUSTER BOX UNIT (CBU)

EXISTING SPRINKLER HEAD

EXISTING CURB AND GUTTER

EXISTING RAILROAD


EXISTING SHRUB

EXISTING STUMP

EXISTING BOULDER

EXISTING MAIL BOX

CIVIL LEGEND



REMOVALS



REMOVE CURB AND GUTTER REMOVE ASPHALT PAVEMENT

REMOVE CONCRETE PAVEMENT REMOVE AGGREGATE SURFACE

PAVEMENT REHAB

UNIFORM MILL & OVERLAY TAPERED MILL & OVERLAY LEVELING COURSE RECLAIM ASPHALT PATCH

CHIP SEAL PAVEMENT

NEW INFLOW CURB AND GUTTER NEW OUTFLOW CURB AND GUTTER NEW ASPHALT SURFACE NEW CONCRETE SURFACE NEW GRANULAR SURFACE

NEW CRUSHED CONCRETE SURFACE NEW DECORATIVE COLORED CONCRETE NEW ASPHALT SIDEWALK/MULTI-USE PATH NEW CONCRETE SIDEWALK/MULTI-USE PATH (Participate Section NEW CONCRETE APPROACH/DRIVEWAY NEW DETECTABLE WARNING PANEL NEW GRAVEL APPROACH/DRIVEWAY

NEW CONCRETE VALLEY GUTTER

NEW ADA RAMP W/WARNING PANEL

DISTURBANCE AREA / TOPSOIL REMOVAL

NEW MEDIAN NOSE APRON

SOIL DISTURBANCE

REMOVE STOCKPILE FXISTING STOCKPILE TEMPORARY STOCKPILE PERMANENT STOCKPILE REAR YARD GRADING

KXXXXXX GRASS BUFFER STRIP

SOIL STABILIZATION

DISTURBED SOIL STABILIZATION

STRAW MULCH SEEDING & STRAW MULCH 3/33/33/73 SEEDING & HYDRO MUI CH TOPSOIL SEEDING & STRAW MULCH TOPSOIL, SEEDING & HYDRO MULCH TOPSOIL, SEEDING & BLANKET

MISCELLANEOUS

EXISTING WETLAND

EXISTING RIPRAP NEW RIPRAP

EXISTING LANDSCAPING AREA NEW LANDSCAPING AREA EXISTING WATER SURFACE NEW WATER SURFACE

EROSION CONTROL

DRAINAGE BREAK LINE <-- -EXISTING DRAINAGE DIRECTION 2.0% FINISHED DRAINAGE DIRECTION & SLOPE

4:1 FINISHED GRADE

EXISTING CONTOUR ELEVATION FINISHED CONTOUR ELEVATION -FL: 900.07 GRADE ELEVATIONS

SEDIMENTATION CONTROL WATTLE SEDIMENTATION CONTROL FENCE

COLOR ROCK CHECK

STABILIZED CONSTRUCTION ENTRANCE

CONCRETE WASHOUT



S.C.E.

INLET PROTECTION DEVICE

ABBREVIATIONS:

BOC = BACK OF CURB BOW = BACK OF WALK C = COMMUNICATION

CB# = STORM SEWER CATCH BASIN

CIPP = CURED IN PLACE PIPE

CL = CENTERLINE

CSP = CORRUGATED STEEL PIPE CO# = SANITARY SEWER CLEANOUT

CS# = CONTROL STRUCTURE

DIA = DIAMETER

DIP = DUCTILE IRON PIPE

F = FLECTRICAL

ECC = EDGE OF CRUSHED CONCRETE

EG = EXISTING GRADE

EOC = EDGE OF CONCRETE

EOG = EDGE OF GRAVEL

EOP = EDGE OF PAVEMENT

FOW = FDGE OF WALK

EX = EXISTING

F = FIBER OPTIC

FES = FLARED END SECTION

FG = FINISHED GRADE

FL = FLOWLINE

FM = FORCEMAIN

G = GAS LINE

HP = HIGH POINT

INV = INVFRT

LP = LOW POINT

MA = MATCH

M# = STORM SEWER MANHOLE

MT# = STORM SEWER TEE MANHOLE

MM# = STORM SEWER MULTI-MANHOLE

MC = MIDPOINT OF CURVE

OHP = OVERHEAD POWER

OHT = OVERHEAD TELEPHONE

OHTV = OVERHEAD TELEVISION

PC = POINT OF CURVATURE

PRC = POINT OF REVERSE CURV

PVC = POLYVINYL CHLORIDE PIPE

PT = POINT OF TANGENCY

RIM = RIM OF STRUCTURE

S# = SANITARY SEWER MANHOLE

S.B. ELEV = STOP BOX ELEVATION

S.S. ELEV = SANITARY SEWER SERVICE INVERT SS = SANITARY SEWER

ST = STORM SEWER

STA = ALIGNMENT STATION

T = TELEPHONE

TOC = TOP OF CONCRETE

TOP = TOP OF PAVEMENT

TOP = TOP OF PIPE

TOW = TOP OF WALK TR# = SANITARY TELEVISING RISER

TRANS = TRANSFORMER

TV = TELEVISION

U = UTILITY (UNKNOWN UTILITY)

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

DANIEL T. ELEMES

DATE: 10.31.2024 LIC. NO. 55420



MAINTENANCE ECT #WR259001 I, MINNESOTA CIVIL
2025 POND M
CITY PROJEC
PLYMOUTH, N DATE: 10.31.2024

REV DATE: EV NUM: RECORD: PROJECT No 24343 MANAGER. JCM DESIGNER QDS DRAFTER: DWA REVIEWER DTE

THE FOLLOWING PLAN NOTES SUPPLEMENT AND AMEND THE PLAN SHEETS. SPECIFICATIONS AND MNDOT REFERENCES AS FOLLOWS:

GENERAL NOTES:

- 1. Take necessary precautions required to protect adjacent properties during the construction operations.
- Notify Engineer where section, subsection or property monuments are encountered, before such monuments are removed. Protect and carefully preserve all property markers and monuments until the engineer and authorized surveyor has witnessed or otherwise referenced the location.
- The removal and replacement of existing street signs are incidental to the installation of the new utility. Replace any damaged signs. Coordinate with homeowners or businesses on the removal/relocation of personal/business affects prior to construction taking place in that area.
- 4. The drawings designate those existing items for removal, replacement, or improvement. If not designated for removal, replacement, or improvement, all other existing items within the site to be protected.
- Testing requirements for MNDOT bid item numbers to be in accordance with the MNDOT Schedule of Materials Controls unless otherwise noted.
- Any construction traffic damage to roads, curb, pavement, or any other item not marked for removal shall to be repaired by the contractor at no cost to the owner.
- 7. Contractor shall protect and reinforce areas over pipes to ensure damage is not done to existing utilities. Replacement of damaged utilities is incidental and the responsibility of the contractor.
- All excavated material is the property of the contractor. Contractor must provide the City the address of location excess material is hauled to.

EROSION CONTROL NOTES:

1. All water discharged from dewatering or basin-draining must be discharged in a manner that does not cause nuisance conditions to waters of the State, erosion in receiving water, inundation of wetland, or damage to properties. Appropriate BMPs must be used to treat the water prior to discharge. The contractor must ensure that discharge points are adequately protected from erosion and scour by an energy dissipation device.

- 2. All appropriate erosion and sediment control BMPs must be in place prior to beginning construction.
- 3. Any tracked sediment on paved surfaces must be removed with 24 hours of discovery or as needed. Incidental to project cost.

UNDERGROUND NOTES:

- 1. Coordinate any utility relocations.
- Unless otherwise noted, any removal, relocation, replacement, or bracing of power poles or any other utilities is the responsibility of the Contractor.
- 3. Existing utilities (both public and private) shown on the plans are approximate and may not be complete. It will be the contractor's responsibility to verify and locate any utilities prior to excavation. There will be no additional payment for exploratory time.
- 4. There is a potential for water on the project. It shall be the contractor's responsibility to dewater for constructability.
- 5. The subsurface utility information in this plan is Utility Quality Level D. This quality level was determined according to the guidelines of ASCE 38-02 entitled "Standard Guidelines for the Collection and Depiction of Existing Subsurface Utility Data".
- 6. Not all fittings required for a complete installation may be shown on the plans. Provide all required fittings.
- 7. Verify all existing pipe sizes in the field.

TRAFFIC CONTROL NOTES:

- 1. The contractor shall submit a traffic control plan to the City and Engineer for approval prior to beginning construction. Traffic control must be in place prior to any hauling.
- The contractor will be responsible for maintaining access to all businesses/residences/public facilities at all times. This would include building & maintaining any required temporary access roadways.
- Contractor must follow the current M.U.T.C.D. for traffic control for any and all construction operations that interfere with traffic. The recommended haul route is Carlson Parkway to Xenium Lane to County Road 6.

 Contractor to give no less than 48 hour notice prior to any work being done on the project. All no parking signs and any traffic control shall be posted at least 48 hours prior to work commencing. I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Daniel Elemes

DATE: <u>10.31.2024</u> LIC. NO. <u>55420</u>



CIVIL
2025 POND MAINTENANCE
CITY PROJECT #WR259001
PLYMOUTH, MINNESOTA
GENERAL NOTES

DATE: 10.31.2024


REV DATE: ---
REV NUM: ---
RECORD: ---
PROJECT No. 24343

MANAGER: JCM

DESIGNER: QDS

DRAFTER: DWA

REVIEWER: DTE




DTE

24343 JCM QDS DWA

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.


DANIEL T. ELEMES


DATE: 10.31.2024 LIC. NO. 55420



DETAILS
2025 POND MAINTENANCE
CITY PROJECT #WR259001
PLYMOUTH, MINNESOTA
DETAILS

DATE:	10.31.2024
REV DATE:	
REV NUM:	
RECORD:	
PROJECT N	o. 24343
MANAGER:	JCM
DESIGNER:	QDS
DRAFTER:	DWA
REVIEWER:	DTE





JCM

QDS

DWA

DTE