
CITY OF PLYMOUTH

CONSTRUCTION PLANS FOR:

HAMEL ROAD EXTENSION

CITY PROJECT NO. ST170002



<u>NOTE:</u>

THE PLAN INDICATES THE GENERAL LOCATION OF KNOWN UTILITIES ON THE PROJECT. ALL UTILITY LOCATIONS ARE APPROXIMATE. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL VERIFY ALL UNDERGROUND UTILITY LOCATIONS AND ELEVATIONS WITH THE UTILITY COMPANIES.

THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-02, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA".

 SCALES

 PLAN
 50'

 PROFILE
 50'



GOVERNING SPECIFICATIONS

THE 2024 EDITION OF THE CITY OF PLYMOUTH SPECIFICATIONS SHALL GOVERN, SUPPLEMENTED BY THE 2020 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION".

ALL TRAFFIC CONTROL DEVICES AND SIGNING SHALL CONFORM TO THE LATEST EDITION OF THE "MINNESOTA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MN MUTCD) INCLUDING THE LATEST "FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS".

	SHEET INDEX
SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	STATEMENT OF ESTIMATED QUANTITIES
3	TYPICAL SECTIONS
4 - 21	DETAILS & STANDARD PLANS
22 - 23	ALIGNMENT PLAN
24	EXISTING TOPOGRAPHY AND UTILITIES PLAN
25 - 26	REMOVAL PLAN
27 - 30	CONSTRUCTION PLAN AND PROFILE
31 - 32	DRAINAGE & TURF ESTABLISHMENT & EROSION
	CONTROL PLAN
33 - 34	STORM WATER POLLUTION PREVENTION PLAN

CROSS SECTIONS

THIS PLAN CONTAINS 45 SHEETS



SIGNATURE:	NAME:	KATIE BECKER
DESIGN ENGINEER: I HEREBY CERTIFY THAT T MY DIRECT SUPERVISION, AND THAT I AM A I UNDER THE LAWS OF THE STATE OF MINNESC	OULY LICENSED	
2/6/2025	LICENSE NI	MRFR- 61797



	DATE:
APPROVED: CITY OF PLYMOLITH	

HAMEL ROAD EXTENSION

SHEET NO. 1 OF 45 SHEETS

12: 32: 02 AM 2/6/2025

		STATEMENT OF ESTIMATED QUANTIT	IES	
ITEM NO.	MNDOT ITEM NO.	ITEM	UNITS	TOTAL ESTIMATED QUANTITY
1	2021.501	MOBILIZATION	LUMP SUM	1
2	2101.502	CLEARING	EACH	1
3	2101.502	GRUBBING	EACH	1
4	2104.502	SALVAGE LIGHTING UNIT	EACH	1
5	2104.503	SAWING BIT PAVEMENT (FULL DEPTH)	LIN FT	120
6	2104.503	REMOVE PIPE CULVERTS (3)	LIN FT	24
7	2104.503	REMOVE CURB & GUTTER	LIN FT	133
8	2104.503	REMOVE GUARDRAIL	LIN FT	157
9	2104.503	SALVAGE FENCE	LIN FT	31
10	2104.504	REMOVE BITUMINOUS PAVEMENT	SQ YD	459
11	2104.518	REMOVE BITUMINOUS WALK	SQ FT	87
12	2106.507	EXCAVATION - COMMON (P) EXCAVATION - SUBGRADE (P)	CU YD	3470
13	2106.507	EXCAVATION - SUBGRADE (P)	CU YD	5750
14	2106.507	SELECT GRANULAR EMBANKMENT (CV) (P)	CU YD	1630
15	2106.507		CU YD	4470
16	2211.507	AGGREGATE BASE (CV) CLASS 5 (P)	CU YD	1400
17	2360.509	TYPE SP 12.5 WEARING COURSE MIX (3,C)	TON	470
18	2360.509	TYPE SP 12.5 NON WEARING COURSE MIX (3,C)	TON	470
19	2501.502	15" RC PIPE APRON	EACH	1
20	2502.503	6" PERF PVC PIPE DRAIN	LIN FT	2750
21	2503.503	15" RC PIPE SEWER DES 3006 CL V	LIN FT	161
22	2506.502	CASTING ASSEMBLY (1)	EACH	3
23	2506.502	ADJUST FRAME & RING CASTING	EACH	9
24	2506.503	CONST DRAINAGE STRUCTURE ST-2	LIN FT	4.0
25	2506.503		LIN FT	10
26	2506.602	CONNECT INTO EXISTING DRAINAGE STRUCTURE (SUBDRAIN)	EACH	4
27	2506.602	RECONSTRUCT DRAINAGE STRUCTURE	EACH	1
28	2511.507	RANDOM RIPRAP CLASS III (2)	CU YD	4.8
29	2521.518	6" CONCRETE WALK	SQ FT	465
30	-	3" BITUMINOUS TRAIL	SQ YD	1298
31	2521.602	DRILL & GROUT REINF BAR (EPOXY COATED)	EACH	26
32	2531.503	CONCRETE CURB & GUTTER DESIGN B618	LIN FT	2890
33	2531.618	TRUNCATED DOMES	SQ FT	32
34	2545.602		EACH	1
35		INSTALL FENCE	LIN FT	31
36	2563.601	TRAFFIC CONTROL SUPERVISOR	LUMP SUM	1
37	2563.601	TRAFFIC CONTROL	LUMP SUM	1
38	2564.618	SIGN	SQ FT	131
39	2573.501	STABILIZED CONSTRUCTION EXIT	EACH	2
40	2573.502	STORM DRAIN INLET PROTECTION	EACH	13
41	2573.503	SILT FENCE, TYPE HI	LIN FT	40
42	2573.503		LIN FT	1890
43	2574.505	SUBSOILING	ACRE	0.5
44	2574.505	SOIL BED PREPARATION	CU YD	1.4
45 46	2574.507 2574.508	COMMON TOPSOIL BORROW	POUND	653 120
46	2574.508	FERTILIZER TYPE 1 FERTILIZER TYPE 3	POUND	170
48	2575.504	ROLLED EROSION PREVENTION CATEGORY 35	SQ YD	36
49	2575.504	SEEDING	ACRE	0.9
50	2575.508	HYDRAULIC STABILIZED FIBER MATRIX	POUND	2430
51	2575.608	SEED RESIDENTIAL TURFGRASS	POUND	70
52	2575.608		POUND	20
53	2582.503		LIN FT	122
54	2582.503		LIN FT	1408
	2002.000	T DOODLE SOLID LINE MOETI-COMPONENT	LINI	1700

- NOTES:
 (P) DENOTES PLAN QUANTITY ITEM.
 (1) SEE STORM SEWER TABULATION ON SHEET 32.
 (2) RIPRAP SHALL BE GRANITE.
 (3) PIPE APRON REMOVAL IS INCIDENTAL.


1.


I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.


PRINT NAME: KATIE BECKER


STATEMENT OF ESTIMATED QUANTITIES

HAMEL ROAD EXTENSION SHEETS SHEET NO. 45













THE INTENT OF THESE SPECIFICATIONS IS TO HAVE A UNIFORM TRAFFIC CONTROL SIGNS THROUGHOUT THE CITY. THIS IS IMPORTANT FOR AESTHETIC PURPOSES AND WILL EASE REPAIRS, KEEPING THE NUMBER AND TYPES OF PARTS NEEDED IN INVENTORY TO A THE SPECIFICATIONS INCLUDE, BUT ARE NOT LIMITED TO: REGULATORY, PARKING, SCHOOL, WARNING, PARK AND INFORMATION SIGNS. ALL SIGNAGE SHALL BE SHOWN ON THE STREET PLANS OR A SEPARATE PLAN SHEET FOR THE PROJECT. THE CITY PUBLIC WORKS DEPARTMENT SHALL APPROVE ALL SIGNS AND MATERIALS PRIOR TO INSTALLATION. (SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL) SIGNS:
COMMON SIGN SIZES:
STOP — R1-1, 30" X 30"
"NO PARKING ANY TIME" (SYMBOL W/"ANY TIME" UNDERNEATH)— R7-2A, 12" X 18"
SPEED LIMIT — R2-1, 24" X 30"
STOP AHEAD — W3-1, 36" X 36"
SIGNAL AHEAD — W3-3, 36" X 36"
KEEP RIGHT — R4-7, 24" X 30"
OBJECT MARKER — OM1-2, 18" X 18" (BLACK BACKGROUND W/ YELLOW REFLECTORS)
NO OUTLET — W14-2, 30" X 30" ALL SIGNS SHALL BE LYLE SIGNS OR APPROVED EQUAL.
ALL SIGNS WILL HAVE "3M" HIGH INTENSITY REFLECTIVE SHEETING OR APPROVED EQUAL.
ALL SIGNS SHALL BE ON ALUMINUM PLATE.
ALL SIGNS UP TO 18" SHALL BE 0.800 MIN. THICKNESS.
ALL SIGNS OVER 30" SHALL BE 0.100 MIN. THICKNESS.
ALL SIGNS TO BE SIZED ACCORDING TO MN MUTCD MANUAL.
AND PUNCHED WITH %" HOLES MEETING MN/DOT SPECS.
STREET SIGNS SHALL NOT INCLUDE "N" FOR NORTH POSTS:
THE SIGN SUPPORTS WILL BE EITHER A "U" CHANNEL POST, PAINTED GREEN OR A 3"
DIAMETER, 12' LONG TUBE POST. THE POSTS SHALL BE 2 & 3 LBS. PER FT. AND 6,7
AND 8' IN LENGTH. ALL SIGNS UP TO 18" SHALL BE MOUNTED ON 2 U-CHANNEL
POSTS, EACH 2 LBS., ONE 7' LONG AND ONE 6' LONG. THE LONGER POST TO BE
DRIVEN IN THE GROUND FIRST.
ALL SIGNS 18" TO 30" SHALL USE A 8' — 3 LB. POST AND A 7' — 2 LB. POST, WITH
THE 3LB. POST DRIVEN INTO THE GROUND FIRST.
ALL SIGNS OVER 30" SHALL USE 2 SETS OF POSTS. (THE HEAVIER POST PLACED IN
THE GROUND FIRST)
ALL U-CHANNEL POSTS WILL BE POUNDED 3' INTO THE GROUND. PLACEMENT AND MOUNTING HEIGHTS:
SEE PLATES STRT-21 THROUGH STRT-25
ALL TUBE POST SHALL BE PLACED IN A 10" DIAMETER BY 3' DEEP CONCRETE FOOTING
FLARED AT THE BOTTOM.
IT WILL BE THE RESPONSIBILITY OF THE INSTALLER TO HAVE ALL UNDERGROUND
UTILITIES LOCATED. STANDARD DETAILS P 1-24 TRAFFIC SIGN SPECIFICATIONS CITY PL. NO. STRT-21 REVISED 1-20


CITY OF PLYMOUTH











HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.


KATIE BECKER PRINT NAME: DATE 2/6/2025 LICENSE # 43560


DETAILS & STANDARD PLANS


HAMEL ROAD EXTENSION SHEET NO. SHEETS 4 45


NO DATE DWN CKD REVISIONS


2:58























HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.

KATIE BECKER PRINT NAME: DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. SHEETS 45

CITY OF PLYMOUTH [6"]

(PROJECT NAME) [3"] (PROJECT NO.) [2-1/2"]

PROCEED WITH CAUTION [6"]

FOR INFORMATION: [2-1/2"] (PROJECT WEBPAGE) (763) 509-5500

(CONTRACTOR'S NAME) [2-1/2"] (ADDRESS) (LOCAL PHONE NO.)

SCHEDULED COMPLETION DATE: [2-1/2"] (DATE)

NOTE:
Sign shall be 4' x 6' with a white background with black letters, (no hand lettering) and of proper height to be readily visible from an automobile, and located as directed by engineer. Sign shall be mounted on 4"x 4" posts

() Project Specific Information



STANDARD DETAILS STANDARD CITY PROJECT SIGN CITY OF PLYMOUTH

PUBLISHED 1-24 CITY PL. NO. DWG-1 REVISED 1-22

C: Ov We work:


I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: SIGNATURE:
DATE 2/6/2025 LICENSE # 61797

KATIE BECKER

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. 45 SHEETS 6



10/24/2024 2:58 PM C:\nw working\projectwise\allignt\d0264339\cd2

NO DATE DWN CKD REVISIONS


ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 PRINT NAME:
 KATIE BECKER

 SIGNATURE:
 DATE
 2/6/2025
 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 7 OF 45 SHEETS




NO DATE DWN CKD REVISIONS

BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.

KATIE BECKER PRINT NAME: HEREBY CERTIFY THAT THIS SHEET WAS PREPARED DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. 45 SHEETS



10/24/2024 2:58 PM C:\pw_working\projectwise\qliant\d0264332

NO DATE DWN CKD REVISIONS


ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED

BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.

DETAILS & STANDARD PLANS


HAMEL ROAD EXTENSION
SHEET NO. 9 OF 45 SHEETS



10/24/2024 2:58 PM C:\pw_working\projectwise\alliant\d0264332\cd230

NO DATE DWN CKD REVISIONS

♠ ALLIANT



NO DATE DWN CKD REVISIONS


HEREBY CERTIFY THAT THIS SHEET WAS PREPARED


BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.

KATIE BECKER DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. SHEETS 11 45





FLOW LINE PROFILE RAISE - FAN

NON-CONCRET

BOULEVARD

6

36" MAX. SAWCUT 3" MIN. CURB AND GUTTER 3 T/2 PROPOSED PAR CURB REINFORCEMENT AND GUTTER CURB RAMP REINFORCEMENT DETAILS 24 36" MAX. LANDING LANDING 36" MAX. SEPARATE LANDING (1) ②

6" CONCRETE WALK-

TYPICAL SIDEWALK SECTION WITHIN INTERSECTION CORNER

4" MINIMUM

AGGREGATE BASE

2" MIN.-

SECTION VIEW A-A

THICKENED SECTION THROUGH CURB RAMP FLARES

GENERAL NOTES:

"TABLING" OF CROSSWALKS MEANS MAINTAINING LESS THAN 2% CROSS SLOPE WITHIN A CROSSWALK, IS REQUIRED WHEN A ROADWAY IS IN A STOP OR YIELD CONDITION AND THE PROJECT SCOPE ALLOWS.

RECONSTRUCTION PROJECTS: ON FULL PAVEMENT REPLACEMENT PROJECTS "TABLING" OF ENTIRE CROSSWALK SHALL OCCUR WHEN FEASIBLE.

MILL & OVERLAY PROJECTS: "TABLING" OF FLOW LINES, IN FRONT OF THE PEDESTRIAN RAMP, IS REQUIRED WHEN THE EXISTING FLOW LINE IS GREATER THAN 2%. WARPING OF THE BITUMINOUS PAVEMENT CAN NOT EXTEND INTO THE THROUGH LANE. TABLE THE FLOW LINE TO 2% OR AS MUCH AS POSSIBLE WHILE ADHERING TO THE FOLLOWING CRITERIA;

19 1.0% MIN. CROSS-SLOPE OF THE ROAD
2) 5.0% MAX. CROSS-SLOPE OF THE ROAD
3) "TABLE" FLOW LINE UP TO 4% CHANGE FROM EXISTING SLOPE IN FRONT OF PEDESTRIAN RAMP
4) UP TO 2% CHANGE IN FLOW LINE FROM EXISTING SLOPE BEYOND THE PEDESTRIAN CURB RAMP

NON-CONCRET

BOULEVARD

STAND-ALONE ADA RETROFITS: FOLLOW MILL & OVERLAY CRITERIA ABOVE HOWEVER ALL PAVEMENT WARPING IS DONE WITH BITUMINOUS PATCHING ON BITUMINOUS ROADWAYS AND FULL-DEPTH APRON REPLACEMENT ON CONCRETE ROADWAYS.

RAISING OF CURB LINES SHOULD OCCUR IN VERTICALLY CONSTRAINED AREAS.RAISE THE CURB LINES ENOUGH TO ALLOW COMPLIANT RAMPS OR AS MUCH AS POSSIBLE WHILE ADHERING TO THE FOLLOWING CRITERIA;

1) 1.0% MIN. AND 5.0% MAXIMUM CROSS-SLOPE OF THE ROAD

2) 1.0% MIN. FLOW LINE (ON EITHER SIDE OF PEDESTRIAN RAMP) TO MAINTAIN POSITIVE DRAINAGE

3) 5.0% RECOMMENDED MAX. FLOW LINE

4) LONGITUDINAL THROUGH LANE ROADWAY TAPERS SHOULD BE 1" VERTICAL PER 15' HORIZONTAL





STANDARD PLAN 5-297.250 6 OF 6 PEDESTRIAN CURB RAMP DETAILS APPROVED: 11-04-2021 STATE PROJ. NO. (TH SHEET NO. OF SHEETS

1 TO ENSURE RAMPS AND LANDINGS ARE PROPERLY CONSTRUCTED, ALL INITIAL LANDINGS AT A TOP OF A RAMPED SURFACE (RUNNING SLOPE GREATER THAN 2%) SHALL BE FORMED AND PLACED SEPARATELY IN AN INDEPENDENT CONCRETE POUR. FOLLOW SIDEWALK REINFORCEMENT DETAILS ON THIS SHEET FOR ALL SEPARATELY POURED INITIAL LANDINGS. ② DRILL AND GROUT NO. 4 12" LONG REINFORCEMENT BARS (EPOXY COATED) AT 36" MAXIMUM CENTER TO CENTER MINIMUM 12" SPACING FROM CONSTRUCTION JOINTS. BARS TO BE ADJUSTED TO MATCH RAMP GRADE. BARS TO BE PAID BY EACH.

4 THIS CURB LINE REINFORCEMENT DETAIL SHALL BE USED ON BITUMINOUS ROADWAYS, FOR CONCRETE ROADWAYS, SEE NOTE 6.

(5) CONSTRUCT WITH EXPANSION MATERIAL PER MNDOT SPECIFICATION 3702 TYPES A-E. EXPANSION MATERIAL SHALL MATCH FULL HEIGHT OF ADJACENT CONCRETE. (6) USE AN APPROVED TYPE F (1/4 INCH THICK) SEPARATION MATERIAL. SEPARATION MATERIAL SHALL MATCH FULL HEIGHT DIMENSION OF ADJACENT CONCRETE.

(3) DRILL AND GROUT 2 - NO. 4 X 12" LONG (6" EMBEDDED) REINFORCEMENT BARS (EPOXY COATED). REINFORCEMENT REQUIRED FOR ALL CONSTRUCTION JOINTS. BARS TO BE PAID BY EACH.


HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA. PRINT NAME: KATIE BECKER DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. SHEETS 45

NO DATE DWN CKD REVISIONS

END SILL CURB AT TOP OF CURB RAMP AND DRIVEWAY FLARES.





NO DATE DWN CKD REVISIONS

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE 2/6/2025 LICENSE # 61797

SHEETS SHEET NO. 13 45





			CULVER ¹	Γ INLET A	PRON ①					
			SOD OR REP	P (SQ. YDS.)						
CULVERT DIAMETER	CIRCULAR AND ARCH PIPE METAL APRON (PLATE 3123, PLATE 3122)	CIRCULAR AND ARCH PIPE CONCRETE APRON (PLATE 3100, PLATE 3110)	CIRCULAR AND ARCH PIPE METAL SAFETY APRON 1:4 SLOPE (PLATE 3148)	ARCH PIPE	CORRUGATED	CIRCULAR CORRUGATED METAL PIPE SAFETY APRON 1:4 SLOPE (PLATE 3128)	"A"	''B''	''C''	''D''
15"	9	9	8	8	N/A	N/A	31	1.51	31	13'
18"	13	12	12	14	16	N/A	31	31	31	16'
21"	14	14	14	16	18	14	31	31	31	17'
24''	16	15	16	19	21	17	31	31	3'	18'
27''	N/A	20	N/A	N/A	N/A	N/A	31	4.51	31	20'
30''	23	22	25	30	32	N/A	3'	4.51	31	22'
36''	34	34	39	48	51	37	4.51	4.51	4.51	27'
42''	43	40	51	64	N/A	N/A	4.51	6'	4.51	301
48''	54	50	66	82	N/A	N/A	4.51	7.5'	4.51	34'
54''	65	58	81	102	N/A	N/A	4.5'	9'	4.51	37'
60''	69	59	91	115	N/A	N/A	4.51	9'	4.51	391
66''	69	63	N/A	N/A	N/A	N/A	4.51	91	4.51	391
72''	78	72	99	122	N/A	N/A	4.5'	10.51	4.51	41'

			CULVERT (DUTLET AF	'RON①					
			SOD OR REP	P (SQ. YDS.)						
CULVERT DIAMETER	CIRCULAR AND ARCH PIPE METAL APRON (PLATE 3123, PLATE 3122)		CIRCULAR AND ARCH PIPE METAL SAFETY APRON 1:4 SLOPE (PLATE 3148)	ARCH PIPE METAL SAFETY APRON 1:6 SLOPE	CORRUGATED METAL PIPE SAFETY APRON 1:6 SLOPE	CIRCULAR CORRUGATED METAL PIPE SAFETY APRON 1:4 SLOPE (PLATE 3128)	"A"	"B"	''C''	ייםיי
15"	10	10	9	10	N/A	N/A	4.51	1.5'	3'	13'
18"	13	13	12	14	15	N/A	6'	1.5'	3'	14'
21''	16	14	16	18	19	15	6'	1.5'	3'	15'
24''	18	18	18	21	22	18	7.5'	1.5'	3'	16'
27''	N/A	19	N/A	N/A	N/A	N/A	7.5'	1.5'	31	17'
30"	23	23	24	28	29	N/A	91	1.5'	31	181
36"	36	35	38	47	48	37	10.5'	1.5'	4.5'	23'
42''	43	40	47	58	N/A	N/A	12'	1.5'	4.51	25'
48''	50	46	57	70	N/A	N/A	13.5'	1.5'	4.51	27'
54''	57	50	67	84	N/A	N/A	15'	1.5'	4.51	291
60"	74	63	90	113	N/A	N/A	16.5'	1.5'	6'	33'
66''	75	67	N/A	N/A	N/A	N/A	16.5'	1.5'	6'	33'
72"	77	70	92	114	N/A	N/A	16.5'	1.5'	6	34'

NOTES:

REPP = ROLLED EROSION PREVENTION PRODUCT.

AREA SHOWN IN SQUARE YARDS IS FOR ONE CULVERT END.

QUANTITIES ARE CALCULATED TO INCLUDE SOD REQUIRED TO PROVIDE A 3"OVERLAP ON ALL 18" WIDE ROLLS. THIS ALLOWS FOR SHRINKAGE OF THE SOD.

FOR PIPE ARCHES USE EQUIVALENT PIPE DIAMETER TO APPROXIMATE AREA.

FOR CORRUGATED POLYETHYLENE PIPE METAL APRON (PLATE 3129), USE THE METAL APRON COLUMN (PLATE 3123).

AREAS AND DIMENSIONS ARE APPROXIMATE AND ARE BASED ON APRON SIDE SLOPES OF NO STEEPER THAN 1:2, UNLESS INDICATED AS FOR SAFETY APRONS.

CARE SHOULD BE TAKEN IN SELECTING SOD TO STABILIZE THE APRON. RIP-RAP SHOULD BE USED FOR FLOW VELOCITIES GREATER THAN 6 FPS.

LEAD EXPER OFFIC		PERMANENT EROSION (TURF ESTABLISHMENT DETAIL AT (APPROVED: 01-08-2020 REVISED:	THOMAS STYRBICKI STATE DESIGN ENGINEER	STANDARD PLAN 5-297.404	2 OF 3
			STANDARD F	DI ANI	STATE PROJ. NO.	SHEET NO.	
	DEPARTMENT OF TRANSPORTATION		SIANDARD F	LAN	TRUNK HWY.	TOTAL SHEE	TS


NO DATE DWN CKD REVISIONS ALLIAN

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 14 OF 45 SHEETS

C:\pw_working\projectwise\alliant\d0264332\cd230121-de



10/24/2024 2:58 PM C: \pw_working\projectwise\alliant\d0264332\cd23

NO DATE DWN CKD REVISIONS ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.


SHEET WAS PREPARED SUPERVISION AND THAT ESSIONAL ENGINEER SIGNATURE: KATIE BECKER

SIGNATURE:

DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 15 OF 45 SHEETS



10/24/2024 2:58 PM C: \pw_working\projectwise\alliant\d0264332\cd2


NO DATE DWN CKD REVISIONS

ALLIANT

T I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DETAILS & STANDARD PLANS


HAMEL ROAD EXTENSION
SHEET NO. 16 OF 45 SHEETS




ROCK DITCH CHECKS FILTER BERMS TYPE 3 (ROCK WEEPER) OR FILTER TYPE 5 (ROCK) 3 FOR USE ON ROUGH-GRADED AREAS ONLY FOR USE OUTSIDE CLEAR ZONE @

BOTTOM OF UPPER CHECK SHOULD BE SAME ELEVATION AS THE TOP OF THE LOWER CHECK TO PROVIDE FOR POOLING FILTER BERM TYPE 3 OR 5 SPACING (Y) DETERMINED BY FORMULA (SEE NOTES)

> DITCH CHECK SPACING FOR ALL FILTER BERM TYPES



SEDIMENT CONTROL LOG TYPE REPP (BLANKET) SYSTEM @



SEDIMENT CONTROL LOG TYPE WOOD FIBER, OR TYPE COMPOST (5) FOR USE ON ROUGH GRADED AREAS

REPP = ROLLED EROSION PREVENTION PRODUCT.

SEE SPECS. 2573, 3601, 3733, 3885, 3886 & 3889.

FOR DITCH CHECKS, PLACE SEDIMENT CONTROL LOG PERPENDICULAR TO FLOW AND IN A CRESCENT SHAPE WITH THE ENDS FACING UPSTREAM.

APPROXIMATE SPACING BETWEEN EACH DITCH CHECK SHOULD BE DETERMINED FROM THE FOLLOWING SPACING FORMULA: DITCH CHECK HEIGHT (FT.)

APPROXIMATE SPACING OF DITCH CHECKS (FT.) = Y = -% CHANNEL SLOPE

- ① POINT "A" MUST BE A MINIMUM OF 6" HIGHER THAN POINT "B" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.
- (2) ROCK DITCH CHECKS PLACED WITHIN THE CLEAR ZONE ARE TO BE 18" OR LESS IN HEIGHT. A 1:6 APPROACH AND DEPARTURE SLOPE SHALL BE PROVIDED.
- 3 DITCH GRADE 3% 5%, MAX. FLOW VELOCITY 12 FT./SEC.
- 4 DITCH GRADE 1.5% 3%, MAX. FLOW VELOCITY 4.5 FT./SEC.
- 5 DITCH GRADE 1.5% 3%, MAX. FLOW VELOCITY 1.5 FT./SEC.

EXPERT CHIEF ENVIRONMENTAL OFFICER OFFICE ENVIRONMENTAL STEWARDSHIP	TEMPORARY SEDIMENT CONTROL DITCH CHECK	APPROVED: 01-08-2020 REVISED:	1 /1 8M S/M	STANDARD PLAN 5-297.405	3 OF 8	
l mn	STANDAR	D DI AN	STATE PROJ. NO.	SHEET NO.		
DEPARTMENT OF TRANSPORTATION	SIANDAN	DPLAN	TRUNK HWY.	TOTAL SHEET	TS	


NO DATE DWN CKD REVISIONS

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. 45 SHEETS




10/24/2024 2:58 PM C: \pw_working\projectwise\alliant\d0264332\

ALLIANT

NT I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 18 OF 45 SHEETS



10/24/2024 2:58 PM C:\pw_working\projectwise\alliant\d0264332\cd;

NO DATE DWN CKD REVISIONS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

HIS SHEET WAS PREPARED (CT SUPERVISION AND THAT ROFESSIONAL ENGINEER STATE OF MINNESOTA.


PRINT NAME: KATILE BECKER

SIGNATURE:

DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 19 OF 45 SHEETS



10/24/2024 2:38 PM C:\pw_working\projectwise\alliant\d02643

NO DATE DWN CKD REVISIONS


ALLIANT

T HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE:
DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION
SHEET NO. 20 OF 45 SHEETS



LEAD EXPERT OFFICE	LYNN CLARKOWSKI CHIEF ENVIRONMENTAL OFFICER OFFICE OF ENVIRNOMENTAL STEWARDSHIP		TEMPORARY EROSION O TEMPORARY POLY COVER		APPROVED: 02-28-2017 REVISED:	THOMASSTYRBICKI STATE DESIGN ENGINEER	STANDARD PLAN 5-297.409	1 OF 1
		m		STANDARD I	DI AN	STATE PROJ. NO.	SHEET NO.	
		DEPARTMENT OF TRANSPORTATION		SIANDARD	LAN	TRUNK HWY.	TOTAL SHEE	.TS


NO DATE DWN CKD REVISIONS

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: KATIE BECKER DATE 2/6/2025 LICENSE # 61797

DETAILS & STANDARD PLANS

HAMEL ROAD EXTENSION SHEET NO. SHEETS 45



	ALIGNMENT DATA HAMEL ROAD													
SEGMENT NUMBER	BEGINNING STATION	ENDING STATION	PI STATION	NOTES	DELTA	DEGREE	RADIUS (FT)	TANGENT (FT)	LENGTH (FT)	BEGINNING COORDINATES NORTHING	BEGINNING COORDINATES EASTING	ENDING COORDINATES NORTHING	ENDING COORDINATES EASTING	AZIMUTH
L100	100+00.00	103+38.18							338.18	188547.03	467051.01	188311.02	467293.21	134"15'26"
C100	103+38.18	106+75.74	105+53.02		89*57'28"	26°38'57.12"	215.00	214.84	337.56	188311.02	467293.21	188007.11	467297.27	134°15'26" 224°12'54"
L101	106+75.74	108+14.66							138.92	188007.11	467297.27	187907.54	467200.39	22412'54"
C101	108+14.66	110+03.06	109+23.57		71°57'57"	38*11'49.87"	150.00	108.91	188.41	187907.54	467200.39	187733.09	467175.15	22412'54" 15214'58"
L102	110+03.06	111+93.79							190.72	187733.09	467175.15	187564.31	467263.96	152°14'58"
C102	111+93.79	113+58.13	112+85.30		62*46'34"	38*11'49.87"	150.00	91.52	164.35	187564.31	467263.96	187484.16	467398.08	152°14'58" 89°28'23"
L103	113+58.13	118+00.00							441.87	187484.16	467398.08	187488.22	467839.93	89°28'23"

						41.101	UN AFFIT	D 4 T 4						
	ALIGNMENT DATA TRAIL 2													
SEGMENT NUMBER	BEGINNING STATION	ENDING STATION	PI STATION	NOTES	DELTA	DEGREE	RADIUS (FT)	TANGENT (FT)	LENGTH (FT)	BEGINNING COORDINATES NORTHING	BEGINNING COORDINATES EASTING	ENDING COORDINATES NORTHING	ENDING COORDINATES EASTING	AZIMUTH
L200	2000+00.00	2000+69.11							69.11	187507.17	467726.06	187507.81	467795.17	89*28'23"
C200	2000+69.11	2000+93.08	2000+81.20		18"18'38"	76°23'39.74"	75.00	12.09	23.97	187507.81	467795.17	187504.23	467818.77	89°28'23" 107°47'02"
C201	2000+93.08	2001+19.61	2001+06.46		18"18'38"	69*01'51.81"	83.00	13.38	26.53	187504.23	467818.77	187500.27	467844.88	107°47'02" 89°28'23"
L201	2001+19.61	2001+50.00							30.39	187500.27	467844.88	187500.55	467875.27	89°28'23"

NO DATE DWN CKD REVISIONS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED
BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.


PRINT NAME: KATIE BECKER SIGNATURE:


DATE 2/6/2025 LICENSE # 61797


HAMEL ROAD EXTENSION SHEET NO. 23

45

SHEETS









SIGNATURE:


DATE 2/6/2025 LICENSE # 61797

HAMEL ROAD - STA 112+50 TO END PROJECT

SHEET NO. 26 45 SHEETS







	SIGN TABULATION								ST		
SIGN NO.	QTY.	POST	MTG HT. (FT.)	PANEL					0005		
		NO. & TYPE			SIGN SIZE (INCH)		AREA (SQ. FT.)	TOTAL AREA (SQ. FT.)	CODE NO.	PANEL LEGEND	
C-1	8	2-SQ	7	18	Χ	24	3.00	24.00	W1-8R	CHEVRON ALIGNMENT — LEFT	
	0			18	Χ	24	3.00	24.00	W1-8L	CHEVRON ALIGNMENT — RIGHT	
C-2	1	1-SQ	7	30	Χ	30	6.25	6.25	W1-1L	SHARP LEFT TURN	
				18	Χ	18	2.25	2.25	W13-1P	20 MPH ADVISORY SPEED PLAQUE	
C-3	1	1-SQ	7	30	Χ	30	6.25	6.25	W1-1L	SHARP LEFT TURN	
				18	Χ	18	2.25	2.25	W13-1P	20 MPH ADVISORY SPEED PLAQUE	
				24	Χ	24	4.00	4.00	R8-3	NO PARKING	
C-4	2	1-SQ	7	30	Χ	30	6.25	12.50	W1-1R	SHARP RIGHT TURN	
				18	Χ	18	2.25	4.50	W13-1P	20 MPH ADVISORY SPEED PLAQUE	
C-5	1	1-SQ	7	30	Χ	30	6.25	6.25	W11-2	PEDESTRIAN CROSSING	
				24	Χ	12	2.00	2.00	W16-7P	DIAGONAL DOWNWARD ARROW	
C-6	1	1-SQ	7	30	Χ	30	6.25	6.25	W11-2	PEDESTRIAN CROSSING	
				24	Χ	12	2.00	2.00	W16-7P	DIAGONAL DOWNWARD ARROW	
				24	Χ	24	4.00	4.00	R8-3	NO PARKING	
C-7	6	1-SQ	7	24	Χ	24	4.00	24.00	R8-3	NO PARKING	
TOTAL								1.31			

C. /pw_working/projectwii

ALLIANT


I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED
BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.


PRINT NAME: KATIE BECKER SIGNATURE:

DATE 2/6/2025 LICENSE # 61797

CONSTRUCTION PLAN AND PROFILE

HAMEL ROAD EXTENSION SHEET NO. 30 45 SHEETS





MEDINA

T118N R23W

RECEIVING WATERS

PROJECT LOCATION

HAMEL ROAD EXTENSION

THE HAMEL ROAD EXTENSION PROJECT COMPLETES A GAP IN HAMEL ROAD SOUTHEAST OF THE TH 55 AND CR 101 INTERSECTION. THE SCOPE OF THIS PROJECT INCLUDES: GRADING, AGGREGATE BASE, BITUMINOUS SURFACING, BITUMINOUS TRAIL, PEDESTRIAN RAMPS, CURB & GUTTER, STORM SEWER, AND SIGNING.

RECEIVING WATERS

RECEIVING WATERS LOCATED WITHIN ONE MILE AERIAL RADIUS) OF THE PROJECT LIMITS ARE IDENTIFIED ON THE USGS 7.5 MIN QUAD MAP. THE FOLLOWING IMPAIRED WATERS ARE LOCATED WITHIN ONE MILE (AERIAL RADIUS) OF THE PROJECT LIMITS AND RECEIVE RUNDER FROM THE PROJECT SITE

- ELM CREEK EPA—APPROVED IMPAIRMENT FOR BENTHIC MACROINVERTEBRATES BIOASSESSMENTS, CHLORIDE, DISSOLVED OXYGEN, ESCHERICHIA COLI (E. COLI), FISH BIOASSESSMENTS, AND TOTAL SUSPENDED SOLIDS (TSS).
- UNNAMED CREEK EPA—APPROVED IMPAIRMENT FOR BENTHIC MACROINVERTEBRATES BIOASSESSMENTS, CHLORIDE, ESCHERICHIA COLI (E. COLI).

PROJECT PERSONNEL AND TRAINING

THIS SWPPP NARRATIVE WAS PREPARED BY DAVID BAUER, WITH ALLIANT ENGINEERING. HE IS CERTIFIED IN THE DESIGN OF CONSTRUCTION SWPPPS BY THE UNIVERSITY OF MINNESOTA. TRAINING DOCUMENTATION BELOW.

UNIVERSITY OF MINNESOTA

David Bauer

Construction Site Management (May 31 2023)
besign of Construction SWPPP (May 31 2025)

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AN EROSION CONTROL SUPERVISOR IN GOOD STANDING WHO IS KNOWLEDGEABLE AND EXPERIENCED IN THE APPLICATION OF EROSION PREVENTION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES AND CERTIFIED IN CONSTRUCTION SITE MANAGEMENT OR EQUIVALENT. THE EROSION CONTROL SUPERVISOR WILL WORK WITH THE PROJECT ENGINEER TO OVERSEE THE IMPLEMENTATION OF THE SWPPP AND THE INSTALLATION, INSPECTION AND MAINTENANCE OF THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS BEFORE, DURING AND AFTER CONSTRUCTION UNTIL THE NOTICE OF TERMINATION (NOT) HAS BEEN FILED WITH THE MPCA. WORK WILL NOT BE ALLOWED TO COMMENCE UNTIL PROOF OF CERTIFICATION HAS BEEN PROVIDED TO THE PROJECT ENGINEER.

THE PRIME CONTRACTOR SHALL PROVIDE AT LEAST ONE CERTIFIED INSTALLER FOR EACH CONTRACTOR OR SUBCONTRACTOR THAT INSTALLS THE PRODUCTS LISTED IN SPECIFICATION SECTION 2573.3.A.2. WORK WILL NOT BE ALLOWED TO COMMENCE UNTIL PROOF OF CERTIFICATION HAS BEEN PROVIDED TO THE PROJECT ENGINEER.

CHAIN OF RESPONSIBILITY

CITY OF PLYMOUTH AND THE CONTRACTOR ARE CO-PERMITTEES FOR THE NPDES CONSTRUCTION PERMIT. THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH ALL ASPECTS OF THE NPDES CONSTRUCTION PERMIT AT ALL TIMES UNTIL THE NOTICE OF TERMINATION (NOT) HAS BEEN FILED WITH THE MPCA. THE CONTRACTOR WILL DEVELOP A CHAIN OF COMMAND WITH ALL OPERATORS ON THE SITE TO ENSURE THAT THE SWPPP WILL BE IMPLEMENTED AND STAY IN EFFECT UNTIL THE CONSTRUCTION PROJECT IS COMPLETE, THE ENTIRE SITE HAS UNDERGONE FINAL STABILIZATION, AND A NOT HAS BEEN SUBMITTED TO THE MPCA.

PROJECT CONTACTS

CITY OF PLYMOUTH AND THE CONTRACTOR ARE RESPONSIBLE FOR IMPLEMENTATION OF THE SWPPP AND INSTALLATION, INSPECTION AND MAINTENANCE OF THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS BEFORE, DURING AND AFTER CONSTRUCTION UNTIL THE NOTICE OF TERMINATION (NOT) HAS BEEN FILED.

ORGANIZATION	CONTACT NAME	TITLE	PHONE
CITY OF PLYMOUTH	TONY MILLER	PROJECT MANAGER	763-509-5528
CONTRACTOR		PROJECT MANAGER	XXX-XXX-XXXX
CONTRACTOR		EROSION CONTROL SUPERVISOR	XXX-XXX-XXXX
MINNESOTA POLLUTION CONTROL AGENCY		MPCA COMPLIANCE AND ENFORCEMENT	507-206-2610

MPCA DUTY OFFICER 24 HOUR EMERGENCY NOTIFICATION: 651-649-5451 TOLL FREE: 800-422-0798

<u>LONG TERM MAINTENANCE AND OPERATION</u>

CITY OF PLYMOUTH IS RESPONSIBLE FOR THE LONG TERM MAINTENANCE AND OPERATION OF THE STORM SEWER SYSTEMS ON CITY ROW. PARK NICOLLET IS IS RESPONSIBLE FOR THE LONG TERM MAINTENANCE OF STORMWATER MANAGEMENT SYSTEMS ON PARK NICOLLET PROPERTY THAT RECEIVE RUNOFF FROM THIS PROJECT.

<u>OCATION OF SWPPP REQUIREMENTS</u>

THE REQUIRED SWPPP ELEMENTS MAY BE LOCATED IN MANY PLACES WITHIN THE PLAN SET AS WELL AS IN THE SPECIAL PROVISIONS, MNDOT SPEC BOOK (2020 EDITION), OR ON FILE WITH THE COUNTY. THE NOTES AND TABLE BELOW ARE INTENDED TO BE A QUICK REFERENCE FOR THE CONTRACTOR AND PROJECT ENGINEER TO USE IN THE FIELD. THERE MAY BE ADDITIONAL REQUIRED SWPPP ELEMENTS INCLUDED ON THE PROJECT THAT ARE NOT LISTED ON THIS SHEET.

LOCATION OF SWPPP REQUIREMENTS IN PROJECT PLAN

· · · · · · · · · · · · · · · · · · ·	
DESCRIPTION	LOCATION
EROSION CONTROL AND TURF ESTABLISHMENT PLAN	SHEET NOS. 31 - 32
DRAINAGE PLAN	SHEET NOS. 31 - 32
STATEMENT OF ESTIMATED QUANTITIES	SHEET NO. 2

STORMWATER CALCULATIONS AND ADDITIONAL HYDRAULIC DESIGN INFORMATION IS AVAILABLE UPON REQUEST.



I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA. PRINT NAME: KATIE BECKER

SIGNATURE:

DATE 2/6/2025 LICENSE # 61797

STORM WATER POLLUTION PREVENTION PLAN

HAMEL ROAD EXTENSION
SHEET NO. 33 OF 45 SHEETS

MILE BOUNDARY

Γ118N R22W

PLYMOUTH

SITE INSPECTION AND MAINTENANCE

Hamel

INSPECT THE ENTIRE CONSTRUCTION SITE A MINIMUM OF ONCE EVERY 7 DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS. INSPECT ALL TEMPORARY AND PERMANENT WATER QUALITY MANAGEMENT, EROSION PREVENTION AND SEDIMENT CONTROL BMPS UNTIL THE SITE HAS UNDERGONE FINAL STABILIZATION AND THE NOT HAS BEEN SUBMITTED. INSPECT SURFACE WATERS FOR SIGNS OF EROSION AND SEDIMENT DEPOSITION. INSPECT CONSTRUCTION SITE VEHICLE EXIT LOCATIONS FOR EVIDENCE OF TRACKING ONTO PAVED SURFACES. INSPECT SURROUNDING PROPERTIES FOR EVIDENCE OF OFF SITE SEDIMENT ACCUMULATION.

RECORD ALL INSPECTIONS AND MAINTENANCE ACTIVITIES IN WRITING WITHIN 24 HOURS. SUBMIT INSPECTION REPORTS IN A FORMAT THAT IS ACCEPTABLE TO THE PROJECT ENGINEER. INCLUDE THE FOLLOWING IN THE RECORDS OF EACH INSPECTION AND MAINTENANCE ACTIVITY:

- A. DATE AND TIME OF INSPECTIONS
- B. NAME OF PERSONS CONDUCTING INSPECTIONS
- C. FINDINGS OF INSPECTIONS, INCLUDING RECOMMENDATIONS FOR CORRECTIVE ACTIONS
- D. CORRECTIVE ACTIONS TAKEN, INCLUDING DATES, TIMES, AND PARTY COMPLETING MAINTENANCE ACTIVITIES.

 E. DATE AND AMOUNT OF ALL RAINFALL EVENTS GREATER THAN 0.5 INCH IN 24 HOURS
- F. DOCUMENTS AND CHANGES MADE TO THE SWPPP

REPLACE, REPAIR OR SUPPLEMENT ALL NONFUNCTIONAL BMPS BY THE END OF THE NEXT BUSINESS DAY FOLLOWING DISCOVERY UNLESS LISTED DIFFERENTLY BELOW:

- A. REPAIR, REPLACE, OR SUPPLEMENT PERIMETER CONTROL DEVICES WHEN IT BECOMES NONFUNCTIONAL OR SEDIMENT REACHES 1/2 THE HEIGHT OF THE DEVICE.
- B. REPAIR OR REPLACE INLET PROTECTION DEVICES WHEN THEY BECOME NONFUNCTIONAL OR SEDIMENT REACHES 1/2 THE HEIGHT AND/OR
- C. REMOVE ALL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS. RESTABILIZE ANY AREAS THAT ARE DISTURBED BY SEDIMENT REMOVAL OPERATIONS. SEDIMENT REMOVAL AND STABILIZATION MUST BE COMPLETED WITHIN 7 DAYS OF DISCOVERY. PREPARE AND SUBMIT SITE MANAGEMENT PLAN FOR WORKING IN SURFACE WATERS. CONTACT ALL APPROPRIATE AUTHORITIES PRIOR TO WORKING IN SURFACE WATERS.
- D. REMOVE TRACKED SEDIMENT FROM PAVED SURFACES BOTH ON AND OFF SITE WITHIN 24 HOURS OF DISCOVERY. STREET SWEEPING MAY HAVE TO OCCUR MORE OFTEN TO MINIMIZE OFF SITE IMPACTS. LIGHTLY WET THE PAVEMENT PRIOR TO SWEEPING.
- E. MAINTAIN ALL BMPS UNTIL WORK HAS BEEN COMPLETED, SITE HAS UNDERGONE FINAL STABILIZATION, AND THE NOT HAS BEEN SUBMITTED TO THE MPCA.

ENVIRONMENTAL REVIEW

THERE ARE NO STORMWATER MITIGATION MEASURES REQUIRED AS A RESULT OF AN ENVIRONMENTAL, ARCHEOLOGICAL OR AGENCY REVIEW. ALL MITIGATION MEASURES HAVE BEEN ADDRESSED IN THIS PLAN SET OR THE SPECIAL PROVISIONS.

THIS PROJECT IS NOT LOCATED IN A WELL HEAD PROTECTION AREA OR DRINKING WATER SUPPLY MANAGEMENT AREA (DWSMA).

STORM WATER POLLUTION PREVENTION PLAN (SWPPP) NARRATIVE - SHEET 2 OF 2

LAND FEATURE CHANGES

ACRES TOTAL DISTURBED AREA: 0.07 TOTAL EXISTING IMPERVIOUS SURFACE AREA: ACRES TOTAL PROPOSED IMPERVIOUS SURFACE AREA: 1.22 ACRES TOTAL PROPOSED NET CHANGE IN IMPERVIOUS SURFACE: 1.15 ACRES

STABILIZATION TIME FRAMES

AREA	TIME FRAME	NOTES
STOCKPILES AND BARE SOIL	WITHIN 7 DAYS	1

INITIATE STABILIZATION IMMEDIATELY WHEN CONSTRUCTION HAS TEMPORARILY OR PERMANENTLY CEASED ON ANY PORTION OF THE SITE. COMPLETE STABILIZATION WITHIN THE TIME FRAME LISTED. IN MANY INSTANCES THIS WILL REQUIRE STABILIZATION TO OCCUR MORE THAN ONCE DURING THE COURSE OF THE PROJECT. TEMPORARY SOIL STOCKPILES WITHOUT SIGNIFICANT CLAY OR SILT AND STOCKPILED AND CONSTRUCTED ROAD BASE ARE EXEMPT FROM THE STABILIZATION REQUIREMENT.

PROJECT SCHEDULE AND CONSTRUCTION PHASING

LAND DISTURBING ACTIVITY WILL BEGIN SPRING 2025 AND BE COMPLETED BY FALL 2025.

CONSTRUCTION WILL BE PHASED AND STAGED TO MINIMIZE THE DURATION OF EXPOSED SOIL AREAS.

GENERAL SWPPP NOTES FOR CONSTRUCTION ACTIVITY

- 1. AMEND THE SWPPP AND DOCUMENT ANY AND ALL CHANGES TO THE SWPPP AND ASSOCIATED PLAN SHEETS IN A TIMELY MANNER. CHANGES TO THE SWPPP SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BY THE EROSION CONTROL SUPERVISOR. STORE THE SWPPP AND ALL AMENDMENTS ON SITE AT ALL TIMES.
- 2. PREPARE AND SUBMIT A SITE MANAGEMENT PLAN FOR THE ENGINEER'S ACCEPTANCE FOR CONCRETE MANAGEMENT, CONCRETE SLURRY APPLICATION AREAS, AREAS IDENTIFIED IN THE PLANS AS "SITE MANAGEMENT PLAN AREA," ANY WORK THAT WILL REQUIRE DEWATERING, AND AS DIRECTED BY THE ENGINEER. SUBMIT ALL SITE MANAGEMENT PLANS TO THE ENGINEER IN WRITING. ALLOW A MINIMUM OF 7 DAYS FOR THE COUNTY TO REVIEW AND ACCEPT SITE MANAGEMENT PLAN SUBMITTALS. WORK WILL NOT BE ALLOWED TO COMMENCE IF A SITE MANAGEMENT PLAN IS REQUIRED UNTIL ACCEPTANCE HAS GRANTED BY THE ENGINEER. THERE WILL BE NO EXTRA TIME ADDED TO THE CONTRACT DUE TO THE UNTIMELY SUBMITTAL.
- 3. IF THE CONTRACTOR DETERMINES THAT DEWATERING ACTIVITIES ARE NECESSARY FOR CONSTRUCTION, A DEWATERING ACTIVITY PLAN SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.
- DO NOT DISTURB AREAS OUTSIDE OF THE CONSTRUCTION LIMITS TO THE MAXIMUM EXTENT PRACTICABLE. DELINEATE AREAS NOT TO BE DISTURBED PRIOR TO STARTING GROUND DISTURBING ACTIVITIES. IF IT BECOMES NECESSARY TO DISTURB AREAS OUTSIDE OF THE CONSTRUCTION LIMITS, OBTAIN WRITTEN PERMISSION FROM THE PROJECT ENGINEER PRIOR TO PROCEEDING. PRESERVE ALL NATURAL
- 5. ROUTE STORMWATER AROUND UNSTABILIZED AREAS OF THE SITE WHENEVER FEASIBLE. PROVIDE EROSION CONTROL AND VELOCITY DISSIPATION DEVICES AS NEEDED TO KEEP CHANNELS FROM ERODING AND TO PREVENT NUISANCE CONDITIONS AT THE OUTLET.
- 6. DIRECT DISCHARGES FROM BMPS TO VEGETATED AREAS WHENEVER FEASIBLE. PROVIDE VELOCITY DISSIPATION DEVICES AS NEEDED TO
- 7. THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS SHALL BE PLACED AS NECESSARY TO MINIMIZE EROSION FROM DISTURBED SURFACES AND TO CAPTURE SEDIMENT ON SITE. ALL SEDIMENT CONTROL MEASURES SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF ANY REMOVAL WORK AND/OR GROUND DISTURBING ACTIVITIES COMMENCE.
- 8. ESTABLISH SEDIMENT CONTROL DEVICES ON ALL DOWN-GRADIENT PERIMETERS AND UP-GRADIENT OF ANY BUFFER ZONES BEFORE ANY UP-GRADIENT LAND DISTURBING ACTIVITIES BEGIN. MAINTAIN SEDIMENT CONTROL DEVICES UNTIL CONSTRUCTION IS COMPLETE AND THE
- 9. LOCATE PERIMETER CONTROL ON THE CONTOUR TO CAPTURE OVERLAND, LOW-VELOCITY SHEET FLOWS DOWN-GRADIENT OF ALL EXPOSED SOILS AND PRIOR TO DISCHARGING TO SURFACE WATERS OR INLETS.
- 10. PROVIDE PERIMETER CONTROL AROUND ALL STOCKPILES. PLACE BMP A MINIMUM OF 5 FEET FROM THE TOE OF SLOPE WHERE FEASIBLE. DO NOT PLACE STOCKPILES IN SURFACE WATERS OR STORMWATER CONVEYANCES.
- 11. PROTECT STORM SEWER INLETS AT ALL TIMES WITH THE APPROPRIATE INLET PROTECTION FOR EACH SPECIFIC PHASE OF CONSTRUCTION. PROVIDE INLET PROTECTION DEVICES WITH EMERGENCY OVERFLOW CAPABILITIES. SILT FENCE PLACED IN THE INLET GRATE IS NOT AN ACCEPTABLE INLET PROTECTION BMP FOR GRADING OPERATIONS. SILT FENCE PLACED IN THE GRATE IS ONLY ALLOWED FOR SHORT INTERVALS DURING MILLING OR PAVING OPERATIONS. INLET PROTECTION DEVICES MAY NEED TO BE PLACED MULTIPLE TIMES IN THE SAME LOCATION OVER THE LIFE OF THE CONTRACT. KEEP ALL STORM SEWER INLET PROTECTION DEVICES IN GOOD FUNCTIONAL CONDITION AT ALL TIMES. REPLACE INLET PROTECTION DEVICE WITH A SUITABLE ALTERNATIVE IF THE PROJECT ENGINEER DEEMS AN INLET PROTECTION DEVICE TO BE NONFUNCTIONAL, IN POOR CONDITION, INEFFECTIVE, OR NOT APPROPRIATE FOR THE CURRENT CONSTRUCTION ACTIVITIES. THERE WILL BE NO COST TO THE CITY FOR REPLACEMENT OF INLET PROTECTION DEVICES
- 12. PROVIDE STABILIZATION IN ANY TRENCHES CUT FOR DEWATERING OR SITE DRAINING PURPOSES.
- 13. SEE SPECIAL PROVISIONS FOR METHODS TO BE USED FOR FINAL STABILIZATION OF ALL EXPOSED SOIL AREAS.
- 14. INPLACE VEGETATION SHALL BE MAINTAINED WHEREVER FEASIBLE. INPLACE TOPSOIL SHALL NOT BE RE-USED. SUBSOILING, SOD, OR SOIL BED PREPARATION PER MNDOT SPEC 2574 SHALL BE PERFORMED TO REDUCE SOIL COMPACTION PRIOR TO PLACING SEED, MULCH, AND

POLLUTION PREVENTION

- 1. PROVIDE A SPILL KIT AT EACH WORK LOCATION ON THE SITE.
- 2. REMOVE TRACKED SEDIMENT FROM PAVED SURFACES DAILY OR AS NEEDED.
- 3. STORE ALL BUILDING MATERIALS THAT HAVE THE POTENTIAL TO LEACH POLLUTANTS, PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS, TREATMENT CHEMICALS, AND LANDSCAPE MATERIALS UNDER COVER AND WITH SECONDARY CONTAINMENT.
- 4. PROVIDE A SECURE STORAGE AREA WITH RESTRICTED ACCESS FOR ALL HAZARDOUS MATERIALS AND TOXIC WASTE. RETURN ALL HAZARDOUS MATERIALS AND TOXIC WASTE TO THE DESIGNATED STORAGE AREA AT THE END OF THE BUSINESS DAY UNLESS INFEASIBLE. STORE ALL HAZARDOUS MATERIALS AND TOXIC WASTE (INCLUDING BUT NOT LIMITED TO OIL, DIESEL FUEL, GASOLINE, HYDRAULIC FLUIDS, PAINT, PETROLEUM BASED PRODUCTS, WOOD PRESERVATIVES, ADDITIVES, CURING COMPOUNDS, AND ACIDS) IN SEALED CONTAINERS WITH SECONDARY CONTAINMENT. CLEAN UP SPILLS IMMEDIATELY.
- 5. STORE, COLLECT AND DISPOSE OF ALL SOLID WASTE.
- 6. POSITION ALL PORTABLE TOILETS SO THAT THEY ARE SECURE AND CANNOT BE TIPPED OR KNOCKED OVER. LOCATE TOILETS AT LEAST 25' AWAY FROM CATCH BASINS, INLETS AND RECEIVING WATERS. TOILETS MUST BE EQUIPPED WITH A SPILL PAN. PROPERLY DISPOSE OF ALL
- 7. FUEL AND MAINTAIN VEHICLES IN A DESIGNATED CONTAINED AREA WHENEVER FEASIBLE. USE DRIP PANS OR ABSORBENT MATERIALS TO PREVENT SPILLS OR LEAKED CHEMICALS FROM DISCHARGING TO SURFACE WATER OR STORMWATER CONVEYANCES. PROVIDE A SPILL KIT AT EACH LOCATION THAT VEHICLES AND EQUIPMENT ARE FUELED OR MAINTAINED.
- 8. LIMIT VEHICLE AND EQUIPMENT WASHING TO A DEFINED AREA OF THE SITE. CONTAIN RUNOFF FROM THE WASHING AREA TO A TEMPORARY SEDIMENT BASIN OR OTHER EFFECTIVE CONTROL. COLLECT AND PROPERLY DISPOSE OF ALL WASTE GENERATED BY VEHICLE AND EQUIPMENT WASHING. ENGINE DEGREASING IS NOT ALLOWED ON THE SITE.
- 9. PROVIDE EFFECTIVE CONTAINMENT FOR ALL LIQUID AND SOLID WASTES GENERATED BY WASHOUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS. LIQUID AND SOLID WASHOUT WASTES MUST NOT CONTACT THE GROUND OR ENTER STORM DRAINS. DESIGN THE CONTAINMENT SO THAT IT DOES NOT RESULT IN RUNOFF FROM THE WASHOUT OPERATIONS OR
- 10. CREATE AND FOLLOW A WRITTEN DISPOSAL PLAN FOR ALL WASTE MATERIALS. INCLUDE IN THE PLAN HOW THE MATERIAL WILL BE DISPOSED OF AND THE LOCATION OF THE DISPOSAL SITE. SUBMIT PLAN TO THE PROJECT ENGINEER.
- 11. USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT DISCHARGE OR PLACEMENT OF BITUMINOUS GRINDINGS, CUTTINGS, MILLINGS, AND OTHER BITUMINOUS WASTES FROM AREAS OF EXISTING OR FUTURE VEGETATED SOILS AND FROM ALL WATER CONVEYANCE SYSTEMS, INCLUDING INLETS. DITCHES AND CURB FLOW LINES.
- 12. USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT CONCRETE DUST, PARTICLES, CONCRETE WASH OUT, AND OTHER CONCRETE WASTES FROM LEAVING THE RIGHT OF WAY, DEPOSITING IN EXISTING OR FUTURE VEGETATED AREAS, AND FROM ENTERING STORMWATER CONVEYANCE SYSTEMS, INCLUDING INLETS AND CURB FLOW LINES. USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT SAW CUT SLURRY AND PLANING WASTE FROM LEAVING THE RIGHT OF WAY AND FROM ENTERING STORMWATER CONVEYANCE SYSTEMS.

FINAL STABILIZATION REQUIREMENTS

THESE NOTES ALONG WITH THE REQUIREMENTS IN THE NPDES CONSTRUCTION STORMWATER PERMIT DEFINE THE REQUIREMENTS THE CONTRACTOR SHALL MEET FOR FINAL STABILIZATION. FINAL STABILIZATION SHALL BE DEFINED AS:

- 1. UNIFORM PERENNIAL VEGETATIVE COVER ESTABLISHED TO 70% DENSITY OF ITS EXPECTED FINAL GROWTH
- 2. ALL DRAINAGE SWALES OR DITCHES ARE STABILIZED
- 3. ALL TEMPORARY SYNTHETIC OR STRUCTURAL BMPS ARE REMOVED
- ALL SEDIMENT CLEANED OUT FROM CONVEYANCES AND BASINS (RETURNED TO FULL DESIGN CAPACITY)

WATER RESOURCES NOTES

THESE NOTES ALONG WITH THE SWPPP NARRATIVE ARE INTENDED TO GIVE INFORMATION ON CRITICAL DRAINAGE FEATURES, NATURAL RESOURCES AND CONTRACTOR OPERATIONS THAT MAY IMPACT DRAINAGE AND NATURAL RESOURCES.

1. THE SIZE AND ELEVATION OF STORM SEWER PIPES AND CATCH BASINS HAVE BEEN SPECIFICALLY DESIGNED TO CONFORM TO MNDOT STATE AID DESIGN STANDARDS AND MPCA PERMIT REQUIREMENTS. CHANGING THESE ITEMS OR THE DIRECTION OF FLOW FROM WHAT IS SHOWN ON THE PLANS MAY CAUSE PROBLEMS OFF THE PROJECT AND COULD MEAN THE PROJECT IS OUT OF COMPLIANCE WITH APPROVED PERMITS. ANY CHANGES TO THE SIZE, ELEVATION OR DIRECTION OF FLOW OF THE DRAINAGE SYSTEM MUST BE APPROVED BY THE ENGINEER OF RECORD.

WATER RELATED PERMITS THAT APPLY TO THIS PROJECT

AGENCY	TYPE OF PERMIT
MINNESOTA POLLUTION CONTROL AGENCY (MPCA)	NPDES STORMWATER CONSTRUCTION PERMIT
ELM CREEK WATERSHED MANAGEMENT COMMISSION (ECWMC)	EROSION AND SEDIMENT CONTROL

NO DATE DWN CKD REVISIONS

102+00.00

AHAMEL ROAD>

Q

1020

1010

1000

30

40

50

60

60


50

990

990

70

70 Ì



0

10


20

30

0

10

20



10/4/2024 12:57 PM
C: \pw_working\projectwise\alliant\d0264335

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

1030₁

1020

1010

1000

990

990 l

_70

-60

-50

-40

-30

-20

-10

-70

-60

-50

-40

-30

-20

-10

 PRINT NAME:
 KATIE BECKER

 SIGNATURE:
 DATE


 DATE
 02/12/25


 LICENSE #
 61797

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 35 OF 45 SHEETS

103+50.00 1030 ₁1030 <HAMEL ROAD> 1020 1020 1010 1010 1000 1000 990 L -70 990 -60 -50 -40 -30 -20 -10 0 10 20 30 40 50 60 70 104+00.00 1030 1030 <HAMEL ROAD> 1020 1020





Mq C; Dw_working Dwn CKD RENSIONS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

 PREPARED
 PRINT NAME:
 KATIE BECKER


 AND THAT
 IGNATURE:
 IGNATURE:

 ESOTA.
 DATE
 02/12/25
 LICENSE #
 61797


CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 36 OF 45 SHEETS


105+00.00











ALLIAN

THE STATE OF THE STATE

LIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED
BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.


PRINT NAME: KATIE BECKER

SIGNATURE:

DATE 02/12/25 LICENSE # 61797

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 37 OF 45 SHEETS




C: \pw_working\projectwise\alignt\dc


ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.


CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 38 OF 45 SHEETS






108+50.00








C: Cpw_working C: Dwn CKD REASIONS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 39 OF 45 SHEETS




10/4/2024 12:57 PM C: \pw_working\projectwise\allia

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 40 OF 45 SHEETS



ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: KATIE BECKER

SIGNATURE:

DATE 02/12/25 LICENSE # 61797

CROSS SECTIONS


HAMEL ROAD EXTENSION
SHEET NO. 41 OF 45 SHEETS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 42 OF 45 SHEETS



10/4/2024 12: 57 PM
C: \pw_working \projectwise \alliant \d

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINT NAME: KATIE BECKER


SIGNATURE:


DATE 02/12/25 LICENSE # 61797

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 43 OF 45 SHEETS

115+50.00






ALLIANT


I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED


BY ME OR UNDER MY DIRECT SUPERVISION AND THAT
I AM A DULY LICENSED PROFESSIONAL ENGINEER
UNDER THE LAWS OF THE STATE OF MINNESOTA.


CROSS SECTIONS


HAMEL ROAD EXTENSION
SHEET NO. 44 OF 45 SHEETS











NO DATE DWN CKD REAISIONS

ALLIANT

I HEREBY CERTIFY THAT THIS SHEET WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

CROSS SECTIONS

HAMEL ROAD EXTENSION
SHEET NO. 45 OF 45 SHEETS